



SOMERO® LINE DRAGON



SLD PULLER



SLD PLACER

If you want to make using concrete pump hoses an even more efficient process, meet the **Somero® Line Dragon, our line-pulling and line-placing system**. These remote-controlled hose-handlers are packed with powerful engines and load-sensing variable-displacement hydraulics that move lines with ease. Besides being the most nimble option on the market, these machines are sure to enhance productivity, create labor savings, and reduce the risk of injury that comes with moving pump hoses by hand.

**Contact us today at Sales@Somero.com / 1-239-210-6519
or visit SOMERO.COM to learn more!**

FEATURES/BENEFITS:

- > Utilizes a Scanreco Remote-control with rechargeable batteries
- > Intelligent Steering adjusts steering angle to prevent stress and damage to components
- > Steering capabilities include two-wheel, four-wheel, and crab-style options
- > Load-sensing variable-displacement hydraulics provide optimal power
- > Return-to-center steering automatically realigns wheels
- > Conveniences include LED work lights, tie-down points for transport, and various clamping locations
- > Jobsite safety is increased

SPECIFICATIONS:

	PULLER	PLACER
WEIGHT	1,150 lbs / 521.6 kg	1,335 lbs / 605 kg
WIDTH	51.5" / 1.3 m	51.5" / 1.3 m
HEIGHT	47" / 1.19 m	49" / 1.24 m
LENGTH	73" / 1.8 m	10' 10" / 3.30 m with boom attached
ENGINE (STANDARD)	11.7 HP / 8.7 kW Honda GX390	
GROUND CLEARANCE	7" - 7.25" / 0.178 -0.184 m	
STEERING ANGLE	180 deg.	
TIRES	Carlisle 18 x 8.5 TireBall High Performance Inflation System	
CLAMP OPENING	8.5" / 10.22 m	

**Engine options & requirements vary based on location. Contact Sales for more information.*



OPTIONS:

- Hose Pan
- Spare Turf Tire
- Spalatter Gaurd Kit
- 4" Plastic Egg
- Optional Leg Tire
- Lift Harness
- 4" Metal Egg
- Hub Cap
- Lift Shackle

WHAT OUR CUSTOMERS SAY:

"A valve stem peeled off one tire at the beginning of a 20,000 sq ft metal deck pour, losing about 35% air pressure. Thanks to TireBalls, we ran all day and completed the pour with zero downtime on a crucial project for us."

- Greg Scurto, **Scurto Cement Construction**



8-Ply Turf Tire + Wheel Assembly with TireBalls